

University Engineering Department

Chandra Shekhar Azad University of Agriculture & Technology, Kanpur

No. CSAE- 180 /2026-27

Dated: 10/06/2026

QUOTATION NOTICE

Sealed quotations are invited by registered/speed post or by Courier for the following work by 16.06.2026 before 2:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer In-charge, University Engineering department on any working day in office hours from 09.06.2026. Quotations will be opened on 16.06.2026 at 1:00 PM in presence of those quotationers who may like to be remain at that time.


University reserves the right to reject any or all the quotations without assigning any reason.

Name of work: Repairing and Panting of Basant Vihar Colony Back Side Block infront of VVIP & VIP Guest House at CSA University Campus Kanpur.

S.L. No	Description of Item	QTY	UNIT	Rate (Rs.)	Amount (Rs.)
1.	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	390.00	Sqm		
2.	12 mm cement plaster of mix 1:6 (1 cement: 6 fine sand)	60.03	Sqm		
3.	Providing and fixing double scaffolding system (cup lock type) on the exterior side, up to seven story height made with 40 mm dia M.S. tube 1.5 m centre to centre, horizontal & vertical tubes joining with cup & lock system with M.S. tubes, M.S. tube challies, M.S. clamps and M.S. staircase system in the scaffolding for working platform etc. and maintaining it in a serviceable condition for the required duration as approved and removing it there after. The scaffolding system shall be stiffened with bracings, runners, connection with the building etc wherever required for inspection of work at required locations with essential safety features for the workmen etc. complete as per directions and approval of Engineer incharge. The elevational area of the scaffolding shall be measured for payment purpose. The payment will be made once irrespective of duration of scaffolding.	75.00	Sqm		
4.	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litres/10 sqm complete including cost of Priming coat.	430.00	Sqm		
Total Rs.					
Add GST @ 18%					
Add Labour Cess @ 1%					
Grand Total Rs.					

CONDITIONS OF QUATATIONS:

1. The firms are requested to mention their GST number on their Pads it is compulsory to write the GST number on the Quotation.
2. Rate shall be inclusive GST & other all taxes and free delivery of University Campus.
3. Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
4. In case of delay of work penalty up to 10% quoted cost may be imposed.
5. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be pa this account.
6. Work to be done strictly as per drawing and specifications and direction of the University Engineer.
7. Copy to Notice Board.
8. In charge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.


(Naushad Khan)
Officer In Charge