

University Engineering Department
Chandra Shekhar Azad University of Agriculture & Technology Kanpur

No. CSAE- 235 File No. 18/2026-27

Dated: 14/6/2026


QUOTATION NOTICE

Sealed quotations are invited by registered/speed post or by Courier for the following work by 18.06.2026 before 2:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer In-charge, University Engineering department on any working day in office hours from office. Quotations will be opened on 18.06.2026 at 3:00 PM in presence of those quotationers who may like to be remain at that time. University reserve the right to reject any or all the quotations without assigning any reason.

Name of work:- Provision of Panel MCCB and cable jointing for Teachers Girls Hostel.

S.No.	Description	Qty	Rate (Rs.)	Amount (Rs.)
1/2.1	Earth work in excavation by mechanical means (Hydraulic excavator) manual means over areas (exceeding 36cm in depth 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in Charge. All kinds of soil.	10 sqm		
2/501	Supply and laying of aluminium conductor PVC insulated armoured served sheathed cables 1100 Volts grade at a depth of 750 mm below ground level over a cushion of 75 mm. thick sand all around and protected with burnt bricks on sides and on top. On surface the cable run shall be fixed on M.S. clamps etc. of suitable size or as directed by the Engineer-Incharge, complete in all respect. The armouring of the cable shall be properly connected with the Earth conductor by clamps etc. (P)150 sq. mm 3-1/2 core	10 mtr		
3/9.3.23	S/M straight through joint with cast resin compound in Fe ferruls and other jointing material for following size of PVC Insulated and PVC sheathed ALPE aluminium conductor cable 1.1 KV grade as required 3.5 X 150 Sq. mm.	02 each		
4/1021(o)	S&F of 250 Amp 4pole MCCB (25kA) Thermal magnetic release cat A L&T make.	01 Nos.		
5.	S&F of Heavy duty H.T. cotton tape.	06 Nos.		
6/504	S&F of Plain or pin type copper tin plated cable socket (Lug) to the cable leads insulating with tape and making connection etc complete in all respects as per direction of the engineer incharge			
	(i) 70 sq. mm	06 each		
	(ii) 150 sq. mm	06 each		
	Total Rs.			
	Add GST @18%			
	Labour cess 1%			
	Total Rs.			

- The firms are requested to mention their GST number on their Pads it is compulsory to write the GST number on the Quotation.
- Rate shall be inclusive GST & other all taxes and free delivery of University Campus.
- Work shall be resumed within same day of the place in order and entire work to be complete within same day.
- In case of delay of work penalty upto 10% quoted cost may be imposed.
- Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid this account.
- Work to be done strictly as per drawing and specifications and direction of the University Engineer.
- Copy to Notice Board.
- Incharge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.


(Naushad Khan)
Officer In Charge