

University Engineering Department
Chandra Shekhar Azad University of Agriculture & Technology Kanpur

No. CSAE- 433 File No.26 /V C Camp/2026-27

Dated: 25/7/2026

Sealed quotations are invited by registered/speed post or by Courier for the following work by 28.07.2026 before 2:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer In-charge, University Engineering department on any working day in office hours from office. Quotations will be opened on 28.07.2026 at 3:00 PM in presence of those quotationers who may like to be remain at that time. University reserve the right to reject any or all the quotations without assigning any reason

Estimate For Electrification Office of ABM Deptt. in CSA Campus.

S.No.	Description	Qty	Rate (Rs.)	Amount (Rs.)
1/405	S&F of batten/angle holder complete in all respects.	08 Nos		
2.	S&F 2.5 Mfd condenser complete Havells Make.	09 Nos		
3.	Replacement of Heavy duty PVC Switch board on wall complete in all respects.			
	(xi) 33x17 cm	10 Nos		
	(xii) 8"x10"	06 Nos		
4.	S&F of 15 watt LED bulb Philips Make.	12 Nos		
5.	S&F of AC power plug with 25Amp MCB and plug complete crab tree make	06 Nos		
6/1139(A)	S&F of power plug with 20Amp/250Volt Flush type modular switch and 5 pin 20A/ 250Volt Flush type modular socket with complete modular box including supply of all material Labour T&P etc.require. proper completion of work.	08 Nos		
7/1006(c)	S&F of 63Amp TP isolator Havells/Legrand	03 Nos		
8/1413	S&F of LED tube light with metal body heavy box type batten light fitting 1x25 watt LED Poly carbonate tube light complete including tube suitable for both surface/suspended catAAA Philips Make.	08 Nos		
9.	Supply & Wiring of submain with 2Nos. 10 Sq.mm.copper conductor FRLSH multistrand wire with in Heavy duty casing one no. 6sqmm copper conductor complete in all respects	80 mtr.		
10/131(c)	Wiring point for light with 1.5sq mm pvc insulated multistrand copper conductor cable in heavy duty pvc conduit with 1.5 sq mm copper conductor cable as earth wire complete in all respects modular switch etc.	12 Nos		
11/134(c)	Wiring point for plug with 1.5 sq mm FRLSH pvc insulated single core copper conductor cable in pvc conduit casing with 1.5 sq mm copper wire as earth wire complete in all respects.	06 Nos		
12.	Supply & Fixing of 12"heavy duty freshair fan complete in all respects including making frame.	02 Nos		
	Total Rs.			
	AddGST.@18%			
	Labour cess1%			
	Total Rs.			

1. Work shall be resumed within same day of the place in order and entire work to be complete within same day.
2. In case of delay of work penalty upto 10% quoted cost may be imposed.
3. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid this account.
4. Work to be done strictly as per drawing and specifications and direction of the University Engineer. .
5. Copy to Notice Board.
6. Incharge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.


(P.K.S. Bhadauria)
Officer In Charge