

University Engineering Department
Chandra Shekhar Azad University of Agriculture & Technology Kanpur

No. CSAE-62 File No.32 /VVIP & VIP Guest House /2026-27

Dated: 21/09 /2026

Sealed quotations are invited by registered/speed post or by Courier for the following work by 23.09.2026 before 2:00 PM. Quotation by ORDINARY POST or BY HAND will not be accepted. Blank quotation form can be taken from the Officer In-charge, University Engineering department on any working day in office hours from office, Quotations will be opened on 23.09.2026 at 3:00 PM in presence of those quotationers who may like to be remain at that time. University reserve the right to reject any or all the quotations without assigning any reason

Electric work (Power Wiring) Department of Soil Conservation And Water Management Lab at CSAU Campus Kanpur

S.L. No	Description of Item	QTY	UNIT	Rate	Amount
1 N/S	Supplying & Laying of 3.5C x 25 sqmm aluminium conductor, A2XWY, 1.1 KV grade, XLPE insulated, FRLS type armoured cable suitable for 415V, 50Hz, AC system with inner and outer PVC sheath. (KEI / Havells make)	50.00	Mtr.		
2N/S	S/F of 25sqmm aluminium lugs complete all in respect.	12.00	Nos.		
3 N/S	Supplying and fixing of L.T. panel complete with ARC Sheet powder coated with 4-pole Busbar 200Amp, Connecting copper wires, Copper Lugs and other accessories, Panel Indicator, Space for 01 Incoming MCCB and 18 Outgoing SP MCB etc.	1.00	Nos.		
4. N/S	Providing and fixing 125A, 25KA, 4-pole MCCB rating and breaking capacity and pole MCCB with thermomagnetic release and terminal spreaders in existing cubicle panel board including drilling holes in cubicle panel, making connections, lcs=100% lcu and Operational Voltage 690V etc. as required. (L&T)	1.00	Nos.		
5 N/S	S/F of heavy duty DBOXx MCB protected socket(4M) with 32 Amp MCB havells carb tree complete.	3.00	Nos.		
6 1139(A)	S&F of power plug with 20Amp/250Volt Flush type modular switch and 5 pin 20A/250Volt Flush type modular socket with complete modular box including supply of all material etc. required proper completion of work.	5.00	Nos.		
7 N/S	Wiring point for plug/Fresh air fan with 1.5 sq mm FRLSH pvc insulated single core copper conductor cable in pvc conduit concealed in wall with 1.0 sq mm copper wire as earth wire complete in all respects with modulator switch.	9.00	Nos.		
8 N/S	S&F of 12inch Plastic make fresh air fan & including making hole replacing glass with acrylic sheet/ply wood complete in all respect including complete frame. Havells	2.00	Nos.		
9 N/S	S/F of 40A C-curve, 10KA MCB. (L&T make)	03.00	Nos.		
10N/S	S/F of 32A C-curve, 10KA MCB. (L&T make)	08.00	Nos.		
11 N/S	Cost of 25 mm dia Heavy duty flexible pipe with PVC coating along with all ancillaries & accessories like coupler etc.	80.00	Mtr.		
12 N/S	Supply and wiring of submain with 2nos. 2.5sqmm copper conductor wire in heavy gauge PVC conduit concealed in the wall with 1nos. 1.5sqmm copper wire as earth wire complete in all respect.	160.00	Mtr.		
13N/S	S/F of heavy duty cotton tape.	3.00	Nos.		
14N/S	S/F of steel grip PVC tape.	1.00	Pkt.		
	Total Rs				
	Add GST 18%				
	Add Labour Cess 1%				
	Grand Total				

1. Work shall be resumed within same day of the place in order and entire work to be complete within same day.
2. In case of delay of work penalty upto 10% quoted cost may be imposed.
3. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid this account.
4. Work to be done strictly as per drawing and specifications and direction of the University Engineer. .
5. Copy to Notice Board.
6. Incharge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.


(P.K.S. Bhadauria)
Officer In Charge