

University Engineering Department

Chandra Shekhar Azad University of Agriculture & Technology, Kanpur

No. CSAU - 723 /2026-27

Dated: 12/10/2026

QUOTATION NOTICE

Sealed quotations are invited by registered/speed post or by Courier for the following work by 13.10.2026 before 12:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer In-charge, University Engineering department on any working day in office hours from 12.10.2026 Quotations will be opened on 13.10.2026 at 1:00 PM in presence of those quotationers who may like to be remain at that time.

University reserves the right to reject any or all the quotations without assigning any reason.

Name of work:- Laying of New sewer line and construction of sewer chamber in Crop Physiology Department at CSAU campus Kanpur

Sl. No	Description	Qty	Unit	Rate (Rs.)	Amount (Rs.)
1	Earth work in excavation by mechanical means (Hydraulic excavator): Manual manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5m. as directed nby Enginner-in-charge. All kinds of Soil	39.00	cum		
2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 1.5 in superstructure above plinth level up to floor V level in all shapes and sizes in Cement mortar 1:6 (1 cement : 6 coarse sand)	1.90	Cum		
3	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	11.00	Sqm		
4	Providing and Laying in position cement concrete of specified grade excludng the cost of centering and shuttering - All work up to plinth level 1:2:4(1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	3.40	Cum		
5	Providing and Laying 150mm dia pvc pipe at required place as per direction of EIC including T & P complete in all respect	48.00	Mtr		
6	S/F manhole lid square at required place as per direction of EIC including T & P complete in all respect	01	Job		
				Total Rs.	
				GST 18 %	
				Labour Cess 1%	
				Grand Total Rs.	
				Say	

CONDITIONS OF QUATATIONS:

1. The firms are requested to mention their GST number on their Pads it is compulsory to write the GST number on the Quotation.
2. Rate shall be inclusive GST & other all taxes and free delivery of University Campus.
3. Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
4. In case of delay of work penalty up to 10% quoted cost may be imposed.
5. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be pai this account.
6. Work to be done strictly as per drawing and specifications and direction of the University Engineer.
7. Copy to Notice Board.
8. In charge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.

[Signature]
72

[Signature]
(P.K.S. Bhadauria)
Officer In Charge