University Engineering Department

Chandra Shekhar Azad University of Agriculture & Technology Kanpur

No. CSAU- 780 2026-27 Dated: 06/11/ 2026

TENDER NOTICE

Sealed Tenders are invited by the following work by 17.11.2026 before 12:00 PM. Tenders by **BY HAND** will not be accepted. Blank Tender form can be taken from the Officer Incharge, University Engineering department on any working day in office hours from 07.11.2026. Tenders will be opened on 17.11.2026 at 1.00 PM in presence of those Tenderers who may like to be remain at that time.

University reserve the right to reject any or all the Tenders without assigning any reason.

Name of work: Electrification of Ground Floor Reading area for Central Library at CSA University Campus Kanpur

S.L. No	Description of Item	QTY	UNIT	Rate as	Amount
1.	S/F of batten angle holder complete in all respects	10	Nos.		
2.	S/F of 2.5 Mft condenser complete Hevells Make	08	Nos.		
3	Replacement of Heavy duty G.I. Switch board cancealed in the wall complete in all repects.				
	(XL) 33x17 cm	10	Nos.		
	(XH) 8"x10"	06	Nos.		
4	S/F of 23 watt LED bulb Philips Make	05	Nos.		
5	S/F of Power plug with 20 Amp 250 Volt Flush type modular switch and 5 pin 30 A 250Volt Flush modular socket with complete modular box including supply of all material Labour T&P etc. required proper completion of work	05	Nos.		
6	S/F of LT Panel complete with ARC sheet powder coated	01	Nos.		
7	S/F of LED tube light with metal body heavy box type batten light fitting 1X25 watt LED Poly carbonate tube light complete including tube suitable for both surface suspended cat AAA Philips Make.	21	Nos.		
8.	**Supply & Wiring** of submain with 2Nos. 10Sq.mm. copper conductor FRLSH multistrand wire with no. 6Sqmm copper conductor complete in all respects	100	Mtr.		
9	Wiring point for light fan concealed in wall with 1.5 sq mm FRLSH pvc insulated multistrand copper conductor cable in heavy duty pvc conduit with 1.5 sq mm copper wire as earth wire complete in respects. Modulor switch & socket crab tree	10	Nos.		
10	Wiring point for plug with 1.5 sq mm FRLSH pvc insulated single core copper conductor cable in pvc conduit concealed in wall with 1.5 sq mm copper wire as earth wire earth wire complete in respects. Modulor switch & socket crab tree	08	Nos		
11.	**Supply & Fixing** of 12" heavy duty fresher fan complete in all respects including making frame Havells make.	01	Nos		
12	S/F of recess surface mounting square 18 watt to 20 watt cutout min 150 mm height LED down lighter having powder coated die cast aluminium housing with heat sink diffuser complete Crompton philips	02	Nos		
13.	Scrubing & painting of old existing GI pipe heaving ceiling Fans and tube lights all.	70	Nos		
14.	S&F of 100 Amp pole isolator Legrand L&K make cat A	02	Nos		
15.	S&F of 160Amp 4 pole MCCB 25 KA Thermal magnetic release L&K make	01	No		
16.	S&F of 32 Amp SP MCB 10 KAc curve L&K make	10	Nos.		
17	S&F of Electronic fan regulator (Modular) 120-280 V.ISI marked on the switch board including making connection complete in all respects.	11	Nos.		
				Total Rs	
				Add GST 18%	
				Add Labour Cess 1%	
				Grand Total	
				Say	

Officer - In-Charge

Terms and Conditions for Tender:

1. The firms are requested to mention their GST number on their letter pads. It is compulsory to mention GST number on the pad of the firm.
2. Rate shall be exclusive GST & other all taxes and material free delivery to University Campus.
3. Considering the importance of the work, time & urgency the works shall be started with in 3 days after getting work order.
4. The Earnest money (EMD) of Rs.4,000/- will be deposited by the tenderer through DD/Banker cheque in favour of Comptroller, C.S.A. University of Agric. & Tech. Kanpur.
5. After six months of satisfactory completion of the work your EMD/security money will be refunded.
6. In case of theft or loss of material at work place, the vendor will be fully responsible.
8. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid this account.
9. Work to be done strictly as per drawing and specifications and direction of the University Engineer
10. In case of delay of work penalty upto 10% quoted cost may be imposed.
12. Incharge A.K.M.U., C.S.A.U. of Agric. & Tech Kanpur uploads for University website.
13. Copy to Notice Board.

(P.K.S. Bhadauria)
Officer In Charge