University Engineering Department
Chandra Shekhar Azad University of Agriculture & Technology
Kanpur

No. CSAE- 785 /2026-27 **Dated:** 06/11/ ,2026

SHORT TERM TENDER NOTICE

Sealed Tenders are invited by registered/speed post or by Courier for the following work by 17.11.2026 before 2:00 PM. Tenders by **ORDINARY POST** or **BY HAND** will not be accepted. Blank Tender form can be taken from the Officer Incharge, University Engineering department on any working day in office hours from 07.11.2026. Tenders will be opened on 17.11.2026 at 3:00 PM in presence of those Tenderers who may like to be remain at that time.

University reserve the right to reject any or all the Tenders without assigning any reason.

Name of work:- Estimate For Electric Renovation work for Pesticide Residue Testing Laboratory, Department of Soil Science & Agriculture Chemistry

S.N.	Description of Item	QTY	UNIT	Rate	Amount
1	S&F of power plug with 20Amp/250Volt Flush type modular switch and 5 pin 20A/ 250Volt Flush type modular socket with complete modular box including supply of all material Labour T&P etc. required proper completion of work.	08	Nos.		
2	S&F of 32Amp modular MCB AC Box with 20 Amp Modular Switch & Socket etc complete in All respects crab tree Make.	06	Nos.		
3	S&F of G.P. Modular Switch but For 6 Module of approved make made U.P. of 1.0 mm thick ISI marked G.I. sheet etc complete in all respects.	08	Nos		
4	S&F of G.P. Modular Switch box as above box 18 Module complete in all respects.	04	Nos.		
5	Invertor wiring in Lab Premises with 1.0 mm copper wire including making connections complete in all respects.	01	Job		
6	Installation of UPS and shifting with box Fixing of 63Amp 4Pole Isolator Cat A complete.	03	Nos.		
7	Wiring Point For Fan/Fresh air Fan with 1.5 sq mm Copper Conductor wire etc. with Modular switch box complete in all respects.	01	No		
8	S&F of 2'x2' 36watt to 46 watt indoor recess/surface mounting LED square shape For Armstrong ceiling Powder coated etc complete cat A Crompton/ Philips.	04	Nos.		
9	Supply and erection of Factory Fabricated and wired metal clad dust and vermin Proof wall mounting busbar Aluminium heavy duty 3 Phase multifunctional support with detachable side covers and shall be suitable For extension on the sides,cable sockets compression qlands and indicating lamp on incoming etc.	01	No		
10	S&F of 200 Amp Four Pole change over switch on 50mm x50mm x6mm angle iron Frame including the cost of labour T&P Painting Proper completion of the work .Havells make..	01	No		
11	S&F of 250Amp 4 Pole MCCB 25 KA thermal magnetic release .L&T Make complete.	03	Nos.		
12	S&F of 325Amp 4 Pole MCCB 25 KA thermal magnetic release .L&T Make complete.	02	Nos		
13	Repairing and welding of doors hinges of existing panel & Painting of Panel complete in all respects.	02	Job.		
14	Supply & laying of aluminium conductor PVC Insulated armoured served sheathed cables 1100 Volts grade at a depth of 750 mm thick sand around protected with burnt bricks etc. P -150sq.mm 3-1/2 core	60	Meter		
15	S/F of Plain or Pin type copper tin plated cable socket (Lug) to the cable leads insulating etc complete in respects. a. 150Sq.m.m.3-1/2 core b- 70Sq.m.m. 3-1/2 core	 18 12	 Nos Nos		
16	S&F of LED street light fitting mandatory driver set having die cast aluminium body and lenses suitable for 110 watt 130 watt with company LOGO Crompton / make cat A. Two Years Warrantee.	02	Nos		
17	Supply & laying of submain with 2 no.10 sqmm with multi stand copper conductor wire with 1 no. 6 sq mm copper conductor wire in PVC conduit complete	150	Meter		
18	Supply & laying of submain as above but 2 no. 6 sq mm copper conductor wire with 1 no.4 sq.mm. Wire with as earth wire in PVC conduit etc.	60	Meter		
19	Supply & laying of 2.5 sq.mm copper conductor wire with 2 no.in	02	Rool		

	&F of 1.5" casing PVC heavy duty complete.	10	Nos		
	S&F of 1" PVC heavy duty Flexible Pipe.	05	Rool		
				Total	
				Add GST 18%	
				Add 1 % Labour Cess	
				Grand Total	

Terms and Conditions for Tender:

1. The firms are requested to mention their GST number on their letter pads. It is compulsory to mention GST number on the pad of the firm.
2. Rate shall be exclusive GST & other all taxes and material free delivery to University Campus.
3. Considering the importance of the work, time & urgency the works shall be started with in 3 days after getting work order.
4. The Earnest money (EMD) of Rs.8,000/- will be deposited by the tenderer through DD/Banker cheque in favour of Comptro ller, C.S.A. University of Agric. & Tech. Kanpur.
5. After six months of satisfactory completion of the work your EMD/security money will be refunded.
6. The ordered Firm has to do an MOU on stamp paper of Rs.100.00 dully signed by the vendor and Comptroller, C.S.A.Univ ersity of Agric. & Tech. Kanpur.
7. In case of theft or loss of material at work place, the vendor will be fully responsible.
8. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid t his account.
9. Work to be done strictly as per drawing and specifications and direction of the University Engineer.
10. In case of delay of work penalty upto 10% quoted cost may be imposed.
11. Incharge A.K.M.U., C.S.A.U. of Agric. & Tech Kanpur uploads for University website.
12. Copy to Notice Board.

(P.K.S. Bhadauriya)
Officer In Charge