University Engineering Department

Chandra Shekhar Azad University of Agriculture & Technology, Kanpur

No. CSAU:- 787 /2026-27 Dated: 06/11/2026

QUOTATION NOTICE

Sealed quotations are invited by registered/speed post or by Courier for the following work by 17.11.2026 before 12:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer In-charge, University Engineering department on any working day in office hours from 07.11.2026 Quotations will be opened on 17.11.2026 at 1:00 PM in presence of those quotationers who may like to be remain at that time.

University reserves the right to reject any or all the quotations without assigning any reason.

Name of work:- Reparing and Painting of sick animal Enclosure back side wall & back side last Enclosure in Diary at CSAU campus Kanpur

Sl. No	Description	Qty	Unit	Rate (Rs.)	Amount (Rs.)
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	156.06	Sqm		
2	12 mm cement plaster of mix : 1:4 (1 cement: 4 fine sand)	12.74	Sqm		
3	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete	116.06	Sqm		
4	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two or more coats applied @ 1.43 ltr/ 10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/ 10 sqm)	296.09	Sqm		
				Total Rs.	
				GST 18 %	
				Labour Cess 1%	
				Grand Total Rs.	
				Say	

CONDITIONS OF QUATATIONS:

1. The firms are requested to mention their GST number on their Pads it is compulsory to write the GST number on the Quotation.
2. Rate shall be inclusive GST & other all taxes and free delivery of University Campus.
3. Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
4. In case of delay of work penalty up to 10% quoted cost may be imposed.
5. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be pay this account.
6. Work to be done strictly as per drawing and specifications and direction of the University Engineer.
7. Copy to Notice Board.
8. In charge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.

(P.K.S. Bhadauria)
Officer In Charge