

University Engineering Department
Chandra Shekhar Azad University of Agriculture & Technology Kanpur
 No. CSAE- 235 /2025-26

Dated: 18/06/2025

QUOTATION NOTICE

Sealed quotations are invited by registered/speed post or by Courier for the following work by 26.06.2025 before 2:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer In-charge, University Engineering department on any working day in office hours from 19.06.2025. Quotations will be opened on 26.06.2025 at 3:00 PM in presence of those quotationers who may like to be remain at that time.


University reserves the right to reject any or all the quotations without assigning any reason.

Name of work: plumbing and Sanitary repairing works in Visitor's bathroom of VC office at CSA University Campus Kanpur

Sl. No	Description of Item	QTY	UNIT	Rate	Amount
1	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge 20 mm nominal dia Pipes	8.00	mtr		
2	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm	6.08	sqm		
3	Providing and fixing water closet white vitreous China Orissa pattern W.C. Pan of size 540X440 mm with integral type footrest with 100 mm sand cast Iron P or S trap, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required:	01	Each		
4	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm or 340x410x265 mm sizes respectively	01	Each		
5	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 580x380x350 mm size.	01	Each		
6	S/F of 100mm PVC pipe under floor with necessary jointing connection for proper completion of work as per direction of EIC	9.00	mtr		
				Total Rs	
				Add GST 18%	
				Add 1 % Labour Cess	
				Grand Total	

CONDITIONS OF QUATATIONS:

1. The firms are requested to mention their GST number on their Pads it is compulsory to write the GST number on the Quotation.
2. Rate shall be inclusive GST & other all taxes and free delivery of University Campus.
3. Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
4. In case of delay of work penalty up to 10% quoted cost may be imposed.
5. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be on this account.
6. Work to be done strictly as per drawing and specifications and direction of the University Engineer.
7. Copy to Notice Board.
8. In charge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.


 (Naushad Khan)
 Officer In Charge