

University Engineering Department
Chandra Shekhar Azad University of Agriculture & Technology Kanpur

No. CSAE- 615 /2025-26

Dated: .2025

QUOTATION NOTICE

Sealed quotations are invited by registered/speed post or by Courier for the following work by 05.08.2025 before 2:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer In-charge, University Engineering department on any working day in office hours from 31.07.2025. Quotations will be opened on 05.08.2025 at 3:00 PM in presence of those quotationers who may like to be remain at that time.


University reserves the right to reject any or all the quotations without assigning any reason.

Name of work: Repairing of Nutrition lab at Textile department of Community Science College at CSA University Campus Kanpur

Sl. No	Description of Item	QTY	UNIT	Rate	Amount
1	12 mm cement plaster of mix 1:6 (1 cement:6 fine sand)	21.92	Sqm		
2	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	175.42	sqm		
3	Repairing and fixing of Rain water pipe as per direction of EIC	01	Job		
4	Supply and Fixing of MS bracket pair	01	Job		
5	Providing and fixing C.P. brass long nose bib cock of approved quality conforming to IS standards and weighing not less than 810 gms. 15 mm nominal bore	02	No.		
6	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete. Flexible pipe 32 mm dia	03	No		
7	Marble stone flooring with 18 mm thick marble stone, as per sample of marble approved by Engineer-in-charge, over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry, including rubbing and polishing complete with : Agaria White	3.68	Sqm		
8	Shifting and fixing of sink with MS brackets for proper completion of the work	01	Job		
9	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. 15 mm nominal dia Pipes	05	Mtr		
				Total Rs	
				Add GST 18%	
				Add 1 % Labour Cess	
				Grand Total	

CONDITIONS OF QUOTATIONS:

1. The firms are requested to mention their GST number on their Pads it is compulsory to write the GST number on the Quotation.
2. Rate shall be inclusive GST & other all taxes and free delivery of University Campus.
3. Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
4. In case of delay of work penalty up to 10% quoted cost may be imposed.
5. Quantities are liable to wide variations on either side even items may be altogether omitted be compensation will be paid this account.
6. Work to be done strictly as per drawing and specifications and direction of the University Engineer.
7. Copy to Notice Board.
8. In charge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.


(Naushad Khan)
Officer In Charge