

UNIVERSITY ENGINEERING DEPARTMENT
C.S.Azad University of Agriculture & Technology, Kanpur-2

No.CSAE-1479 /दीक्षान्त समारोह/2020-21

Dated: March 17, 2021

Sealed quotations are invited by Registered/Speed Post or by Courier for the following work by 20.03.2021 before 2:00 pm. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer Incharge, University Engineering in this deptt. on any working day in office hours from 17.03.2021. Quotations will be opened on 20.03.2021 at 3:00 PM in presence of those quotationers who may like to be remain at that time.


University reserves the right to reject any or all the quotations without assigning any reason.

Name of work: Lighting arrangements of Kailash Bhavan & Varandah of Administrative Block at C.S.A.U.A & T., Kanpur

Sl. No.	Description of items	Qty.	Rate/1	Amt.
1.	S/F of 4x36/40watt fluorescent tube light PHILIPS make	30nos.		
2.	S/F of 40watt Electronic choke PHILIPS make HAVELLS	18nos.		
3.	S/F of 23watt/230volt LED bulb PHILIPS or HAVELLS make on upto 25' height	50nos.		
4.	S/F of 9watt LED bulb PHILIPS/HAVELLS	38nos.		
5.	S/F of batten/Angle Holder complete in all respects	20nos.		
6.	S/F of 6 to 32 Amp SP MCB (10KA) LEGRAND make	10nos.		
7.	S/F of 63Amp DP Isolator Cat A LEGRAND make	02nos.		
8/1413	S/F of 1x22 watt LED Metal body batten fitting complete lumens suitable mounting for on both surface and suspended with 5 years warrantee complete in all respects PHILIPS/HAVELLS make Cat AAA	05nos.		
9/1405	S/F of pendent/suspended mounting 24watt to 32watt LED hanging light having powder coated die cast aluminium housing with heat sink diffuser/reflector and driver set, suitable for 24hours, continuous operation complete in all respects Cat AAA with 5 year warrantee	06nos.		
10.	S/F of heavy duty brass holder on existing roof lights upto 25' height	48nos.		
11.	Supply and Laying of submain with 2no. 4sq.mm. multistrand copper conductor wire PVC insulated with one no 2.5sq.mm PVC insulated multistrand copper conductor wire as earth wire in heavy duty PVC conduit complete in all respects	20Mtr		

CONDITIONS OF QUOTATIONS

1. Rate shall be inclusive GST & other all taxes and free delivery of university campus.
2. Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
3. In case of delay of work penalty upto 10% quoted cost may be imposed.
4. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid this account.
5. Work to be done strictly as per drawings and specifications and direction of the university Engineer.
6. Copy to notice board.
7. Incharge, AKMU


(Vijay Kumar Yadav)
Office In-charge