

UNIVERSITY ENGINEERING DEPARTMENT
Chandra Shekhar Azad University of Agriculture & Technology, Kanpur-2

No.CSAE- 263 /56/2019-20-21-22

Dated: July 19 ,2021

Sealed quotations are invited by Registered/Speed Post or by Courier for the following work by 23.07.2021 before 2:00 pm. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer Incharge, University Engineering in this deptt. on any working day in office hours from 19.07.2021. Quotations will be opened on 23.07.2021 at 3:00 PM in presence of those quotationers who may like to be remain at that time.


University reserves the right to reject any or all the quotations without assigning any reason.

Name of work: Replacement & Jointing of underground cable near Dairy & Soil Conservation Deptt. at C.S.A.U.A& T., Kanpur

Sl.No.	Description of item	Qty.	Rate	Amount
1/501(m)	Supply & laying of aluminium conductor PVC insulated armoured served sheathed cables 1100volts grade at a depth of 750mm below ground level over a cushion 750mm thick sand around and protected with burnt bricks on sides and on top. On surface the cable run shall be fixed on MS clamps etc of suitable size or as directed by the Engineer Incharge complete in all respects. The armouring of the cable shall properly connected with the earth conductor by clamps etc 70Sqmm 3 ^{1/2} core	10meter		
2/9.3.20	Supply & making straight through joint with cast resin compound including ferrules and other jointing materials for following size of PVC insulated and PVC sheathed/XLPE aluminium conductor cable of 1.1KV grade as required 3 ^{1/2} x70Sqmm	01no.		
3	charges for underground fault locator by high quality locator system	01no.		
4/504(h)	S/F of plain or pin type copper tin plated cable socket (lug) to the cable leads insulating with tape and making connection etc complete in all respects as per direction of the Engineer Incharge 70Sq.mm	04nos.		
(k)	150Sq.mm	10nos.		
6	S/F of Heavy duty H.T. cotton tape JOHNSON make	05nos.		

CONDITIONS OF QUOTATIONS

1. Rate shall be inclusive GST & other all taxes and free delivery of university campus.
2. Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
3. In case of delay of work penalty upto 10% quoted cost may be imposed.
4. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid this account.
5. Work to be done strictly as per drawings and specifications and direction of the university Engineer.
6. Copy to notice board.
7. Incharge, A.K.M.U.


(Naushad Khan)
Incharge