

UNIVERSITY ENGINEERING DEPARTMENT

CHANDRA SHEKHAR AZAD UNIVERSITY OF AGRICULTURE & TECHNOLOGY

KANPUR-2

No.CSAE677 /QUOTATION/2021(R-1)

Dated: 20/10/2021

QUATATION NOTICE

Sealed Quotation are Invited by Registered/Speed Post or by Courier for the following work by 26/10/21. At 2:00 PM Quotation by Ordinary Post or by hand will not be accepted. Blank Quotation Form can be taken from the In Charge (Works) in the Deptt. On any working day in office hours from 20/10/21. quotations will be opened on 26/10/21. at 03:00 PM In presence of those quotationers who may like to be remain at that time.

University reserve the right to reject any or all the quotations without assigning any reason .

NAME OF WORK: Repairing work of C-53 C type colony Shri Piyush Patel at Kanpur, Campus


S.No	Description	Qty	Unit	Rate	amount
1	Class -150 brick work in 1:4 cement and coarse Sand in Super Structure including Necessary Cutting and Moulding of Brick as required and also including Honey combed brick in thickness Of Wall 12cm. and below including Supply of all materials Labour and tools and plants etc. Required for Proper Completion if the work	0.65	Per Cubic Meter		
2	15 mm cement Plaster in Single coat on Rough side of single or half Brick Wall For interior up to Floor two level including internal Rounded angles chamfers and rounded angles. not excluding 80mm in girthand finished even and smooth 1cement: 3 coarse sand	23.00	Per Square Meter.		
3	Two coat Oil distemper on previously old distempered surface including Supply of all materials Labour and tools and plants etc. Required for Proper Completion if the work including miner repairing with putty.	302.00	Per Square Meter		
4	Two Coat Painting on Previously Painted old Wood or Steal work including Supply of all materials Labour and tools and plants etc. Required for Proper Completion if the work Paint to be used should confirmed to the ISI no 103-1950	75.00	Per Square Meter		
5	Finishing wall with two coat of Water Proof Cement paint of Approved				

	Quality on Previously Old Treated Surface With This Paint to give an even Shade including Supply of all materials Labour and tools and plants etc. Required for Proper Completion if the work	31.00	Per Square Meter		
6	Scraping old white, colour wash or distemper including disposal of refuse material as directed by engineer-in-charge with a distance of 60 meter	402.00	Per Square Meter		
7	White washing two coat including Supply of all materials Labour and tools and plants etc. Required for Proper Completion if the work	32.00	Per Square Meter		
8	Supply and fixing 5 mm thick china glazed tiles in flooring or in skirting or dado laid with 1:3 cement and approved coarse sand mortar finished with white cement slurry jointing and polishing complete including Supply of all materials Labour and tools and plants etc. Required for Proper Completion if the work(size of tiles up 200x 300mm)	2.10	Per Square Meter.		
9	Granite stone Slabe 18 mm thick morror polished Quater rounded with anteskid lines in trades of staircase full length flooring over 20mm average thick base laid over and jointed with cement slurry mixed with pigment to match the shade of including Rubbing and polishing complete with base of cement mortar 1:4 (1 cement 4 coarse sand) Etc. complete	1.70	Per Square Meter		
10	providing and fixing 1mm thick M.S Sleal door with frame of 40x40x6 mm angle iron and 3 mm M.S gusset plates at the junction and corners, all necessary fitting complete including applying a priming coat of approved steal primer using M.S angle 40x40x6 mm for diagonal braces	2.10	Per Square Meter.		
11	25 mm thick PVC Flush door sutters made out of a one piece multi chamber extruded PVC section of the size of 762x 2.5 mm or less as per requirement with an average wall thickness of 1 mm (+ 0.3 mm) PVC foam and cap of size 32x10 mm are provided on both vertical edges to ensure the overall thickness of 25 mm M.S tube having dimensions 19mmx19mm and 1.0 mm (+0.1 mm) is inserted along the hinge side of the	3.15	Per Square Meter.		

	door core of door sutter should be filled with high density Polyuregare foam as per manufacturers specification and direction of EIC to take up necessary hardware and fixture including the location				
12	providing and fixing white vitreour china orissa patermn W.C. Pan of size 580x440 mm with integral type foot rest with 100 mm sand cast iron P or S trape ,10 lit low level white PVC flushing system including Flush pipe manually controlled device (handle lever) conforming to IS 7231 with all fittings and fixer complete including cutting and making good the walls and floors wherever's required including dismentaling of old W.C pan	one	Each		

CONDITIONS OF QUOTATIONS:

1. Rate shall be inclusive of all taxes and free delivery of University Campus.
2. Work shall be resumed within 03 days of the place in order and entire work to be completed within month.
3. In case of delay of work penalty up to 100% quoted cost may be imposed.\
4. Quantities are liable to vide variations on either side even items may be all together omitted be compensation will be paid this account.
5. Work to be done strictly as per drawing and specifications and direction of the officer In-charge.
6. Copy to notice board.
7. In charge A.K.M.U.,C.S.A.U. of Ag. & Tech. Kanpur uploads for Univ. website.


Officer - In-Charge
University Engineering Department
C.S.A. Univ. of Agri. & Technology
Kanpur-2