

University Engineering Department
Chandra Shekhar Azad University of Agriculture & Technology Kanpur

No. CSAE 820 /21-22(R-1)

Dated- 26.11.2021

Sealed quotations are invited by registered/speed post or by Courier for the following work by 29.11.2021 before 2:00 PM. Quotation by ORDINARY POST or BY HAND will not be accepted. Blank quotation form can be taken from the In Charge (Works) in this deptt. on any working day in office hours from 26-11-2021 Quotations will be opened on 29.11.2021 at 3:00 PM in presence of those quotationers who may like to be remain at that time.


University reserves the right to reject any or all the quotations without assigning any reason.

NAME OF WORK:-Concentina Coil Fencing of C/Y boundary wall at VC camp, Office/Lodge, CSAU Kanpur Campus.

SNo	Description	Qty	Unit	Rate(Rs.)	Amount (Rs.)
1	Structural steel work in single section, fixed with or without connecting plate including cutting, haisting, fixing in position and applying a primary coat of approved steel primer all complete	199.00	P.Kg		
2	Providing and fixing Concentina coil fencing with punched tape Concentina coil 600 mm dia 10 metre openable length (Total length 90 m) having 50 nos rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped 2.40m or 3.00 m about and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of E.I.C. with reinforced barbed tape(RBT)/spring cone(2.5 mm thick) win of high tensile strength of 165 Kg/Sq.m with tape (0.52mm thick) and weight 43.478gm/metre (Cost of M.S. angle, C.C. blocks shall be paid respectively)	67.00	P.R.mt		
3	Painting or Varnishing on iron works in small areas or new wood work with one coat of ready mixed priming paint & Two coat of approved superior quality ready mixed of clear synthetic varnish including supply of all materials, labour and T&P etc. required for proper completion of the work. Paint to be used should confirm to the I.S.I.No. 103 1950	20.50	P.sqm		
4	10mm X 75 to 100mm SS Fastner including supply and fixing as per direction of E.I.C.	93 Nos	Each		

CONDITIONS OF QUATATIONS:

1. Rate shall be inclusive of all taxes and free delivery of University Campus.
2. Work shall be resumed within 03 days of the place in order and entire work to be complete within month.
3. In case of delay of work penalty upto 10% quoted cost may be imposed.
4. Quantities are liable to vide variations on either side even items may be all together omitted be compensation will be paid th account.
5. Work to be done strictly as per drawing and specifications and direction of the officer In Charge.
6. Copy to Notice Board.
7. Incharge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur upload for Univ. website.


(Naushad Khan)
Officer In Charge