

UNIVERSITY ENGINEERING DEPARTMENT
CHANDRA SHEKHAR AZAD UNIVERSITY OF AGRICULTURE & TECHNOLOGY,
KANPUR-2

No. C.S.A.E. 801 / QUOTATION/2021 (R-1)

Dated: 22/11/2021

QUOTATION NOTICE

Sealed quotation are invited by Registered/Speed Post or by Courier for the following work by 22/11/21 at 2:00 P.M. Quotation by ordinary post or by hand will not be accepted. Blank quotation form can be taken from the In charge (Works) in this deptt. on any working day in office hours from 22/11/2021. Quotations will be opened on 24/11/2021 at 3:00 P.M. in presence of those quotationers who may like to be remain at that time.


University reserve the right to reject any or all the quotations without assigning any reason.

NAME OF WORK: Construction of two pillar of Pathology Pump House at C.S.A.U. Kanpur

S. No.	Description	Qty	Unit	Rate	Amount
1-	Excavation in foundation in ordinary soil (Loam clay or sand) l/c lift of two 1.5 mtr. and lead upto 30 mtr. including supply of all material etc. require of proper completion of the work.	4.5	Cumt		
2-	Providing and laying cement concrete in 1:4:8 (one cement 4 fine sand : 8 graded brick ballast of 40 mm) including curing etc.	0.5	cumt		
3-	R.C.C. work with cement approved C/S and 20 mm gauge approved stone ballast in prop. of 1:2:4 in lintel of door or window excluding supply of steel etc. as per schedule	3.25	cumt		
4-	15 mm thick cement plaster in 1:3 one cement and three coarse sand including supply of all material etc. require of proper completion of the work.	14.00	Sqm.		
5-	Finishing wall with two coat of Acrylic smooth external paint of best quality including supply of all material etc. require of proper completion of the work.	14.00	Sqm.		
5-	Mild steel or Iron work on such as Rainforced concrete work of Wrought to required shape of 12 to 32 mm ϕ tor steel including supply of all material etc. require of proper completion of the work.	3.25	Qtls.		

CONDITIONS OF QUOTATIONS:

- 1- Rate shall be inclusive of all taxes and free delivery of University Campus.
- 2- Work shall be resumed within 03 days of the place in order and entire work to be complete within month.
- 3- In case of delay of work penalty upto 10% quoted cost may be imposed.
- 4- Quantities are liable to vide variations on either side even items may be all together omitted be compensation will be paid this account.
- 5- Work to be done strictly as per drawings and specifications and direction of the officer In-Charge.
- 6- Copy to Notice Board.
7. Incharge A.K.M.U, C.S.A.U. of Ag. & Tech. Kanpur Upload for Univ.websit


(Naushad Khan)
Officer in-Charge

UNIVERSITY ENGINEERING DEPARTMENT
CHANDRA SHEKHAR AZAD UNIVERSITY OF AGRICULTURE & TECHNOLOGY,
KANPUR-2

No. C.S.A.E. 802 / QUOTATION/2021 (R-1)

Dated: 22/11/2021

QUOTATION NOTICE

Sealed quotation are invited by Registered/Speed Post or by Courier for the following work by 29/11/2021 at 2:00 P.M. Quotation by ordinary post or by hand will not be accepted. Blank quotation form can be taken from the In charge (Works) in this deptt. on any working day in office hours from 22/11/2021. Quotations will be opened on 29/11/2021 at 3:00 P.M. in presence of those quotationers who may like to be remain at that time.


University reserve the right to reject any or all the quotations without assigning any reason.

NAME OF WORK: Repairing work (Distemper, paint etc.) of V.I.P. Guest House (Room No. 1,2,3,4 and Passage inside) at C.S.A.U. Kanpur

S. No.	Description	Qty	Unit	Rate	Amount
1-	Scraping old white or color wash including Disposal of refuse material as directed by Engineer incharge within a distance of 60 mtr.	432.00	Sqm.		
2-	Finishing wall with two coat Birla Putty on old work including supply of all material labour, T&P etc. required for proper completion of the work.	10.00	Sqm.		
3-	Two coat oil distemper on previous surface including supply of all materials, labour and T&P etc. required for proper completion of the work.	432.00	Sqm.		
4-	Finishing walls with two coats of Apex paint of approved make and quality on new work over and including base coat to give and even shade including supply of all material and labour, material and labour, materials complete as per the direction of E/I.	99.00	Sqm.		
5-	Painting on ironwood work in large areas on old wood work with two coat of approved superior quality ready mix paint of clear synthetic varnish including cost of all materials, labour, materials tools and plants etc. required for proper completion of the work (paint is to be used should confirm to the I.S. No. 103 1950)	104.00	Sqm.		

CONDITIONS OF QUOTATIONS:

- 1- Rate shall be inclusive of all taxes and free delivery of University Campus.
- 2- Work shall be resumed within 03 days of the place in order and entire work to be complete within month.
- 3- In case of delay of work penalty upto 10% quoted cost may be imposed.
- 4- Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid this account.
- 5- Work to be done strictly as per drawings and specifications and direction of the officer In-Charge.
- 6- Copy to Notice Board.
- 7- Incharge A.K.M.U, C.S.A.U. of Ag. & Tech. Kanpur Upload for Univ. websit


(Naushad Khan)
Officer in-Charge

UNIVERSITY ENGINEERING DEPARTMENT
CHANDRA SHEKHAR AZAD UNIVERSITY OF AGRICULTURE & TECHNOLOGY,
KANPUR-2

No. C.S.A.E. 804 / QUOTATION/2021 (R-1)

Dated: 23/11/21

QUOTATION NOTICE

Sealed quotation are invited by Registered/Speed Post or by Courier for the following work by 29.11.2021 at 2:00 P.M. Quotation by ordinary post or by hand will not be accepted. Blank quotation form can be taken from the In charge (Works) in this deptt. on any working day in office hours from -- 23.11.2021 Quotations will be opened on 29.11.2021 at 3:00 P.M. in presence of those quotationers who may like to be remain at that time.


University reserve the right to reject any or all the quotations without assigning any reason.

Name of work: **Apex painting work of International Hostel at C.S.A.U. Kanpur.**

S. No.	Description	Qty	Unit	Rate	Amount
1-	Finishing wall with two coat of acrylic smooth Exterior paint of best quality i/c supply of all material, labour, T&P etc. required for proper completion of the work	590.00	sqm		

CONDITIONS OF QUOTATIONS:

- 1- Rate shall be inclusive of all taxes and free delivery of University Campus.
- 2- Work shall be resumed within 03 days of the place in order and entire work to be complete within month.
- 3- In case of delay of work penalty upto 10% quoted cost may be imposed.
- 4- Quantities are liable to vide variations on either side even items may be all together omitted be compensation will be paid this account.
- 5- Work to be done strictly as per drawings and specifications and direction of the officer In-Charge.
- 6- Copy to Notice Board.
- 7- Incharge A.K.M.U, C.S.A.U. of Ag. & Tech. Kanpur Upload for Univ.websit


(Naushad Khan)
Officer in-Charge