

UNIVERSITY ENGINEERING DEPARTMENT
Chandra Shekhar Azad University of Agriculture & Technology, Kanpur-2

No.CSAE- /F.No.32/VVIP & VIP Guest House/2021-22

Dated: Dec. 20, 2021

Sealed quotations are invited by Registered/Speed Post or by Courier for the following work by 24.12.2021 before 2:00 pm. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Incharge, University Engineering in this deptt. on any working day in office hours from 20.12.2021. Quotations will be opened on 24.12.2021 at 3:00 PM in presence of those quotationers who may like to be remain at that time.


University reserves the right to reject any or all the quotations without assigning any reason.

Name of work: Electric Repairing of VIP & VVIP Guest House at Kanpur Campus Room No.1,2,3,4

Sl.No.	Description of item	Qty.	Rate	Amount
1.	S&F of 4x36Watt tube light PHILIPS make	10nos.		
2/1201	S&F of 36watt Electronic choke PHILIPS/HAVELLS.	24nos.		
3.	S&F of 2.5Mfd condenser HAVELLS make	15nos.		
4/405	S&F of batten/Angle Holder complete in all respects.	10nos.		
5.	S&F of 6Amp Modular switch CRABTREE make on existing board.	20nos.		
6.	S&F of 6Amp Modular Socket CRABTREE make	25nos.		
7.	S&F of 16Amp Modular Socket CRABTREE make	15nos.		
8.	S&F of 16Amp Modular switch CRABTREE make.	15nos.		
9.	S&F of 6 Module GI switch board with sheet.	04nos.		
10/1102	S&F of Call bell complete in all respects.	01nos.		
11	S&F of 12" 300mm Electronic Exhaust fan 220/240Volt 1350RPM HAVELLS make metal body.	03nos.		
12	S&F of 9watt LED complete in all respects.	10nos.		
13.	S&F of 14watt 230volt PHILIPS/HAVELLS make	15nos.		
14.	S&F of 23watt LED complete in all respects.	06nos.		
15.	Replacement of 25liter Geyser element 1500watt complete	05nos.		
16.	Replacement of 25liter Geyser Thermostat	03nos.		
17/1139	S&F of power plug with 15A/250Volt flush type siitch & 5 Pin 15A/250volt flush type in suitable M.S.Box of 175mmx100mmx 50mm size with Phenolic laminated sheet cover 3mm thick fixed with brass machine screws and cup washer.	02nos.		
18/1413	S&F of 1x22watt LED metal body batten fitting complete lumens suitable mounting for both surface & Suspended with warrantee complete in all respects PHILIPS/HAVELLS Cat AAA	06nos.		
19/1203 (C)	S&F of Electronic fan regulator (Modular) 120-280V ISI marked on the existing switch board including making connections required material T&P etc.	02nos.		
20/218 (C)	Supply & Wiring of submain with 2no. 10Sq.mm. FRLSH PVC insulated 1100Volt grade multistrand single core copper conductor cable in 25mm dia PVC conduit concealed in the wall with one no. 6Sqmm PVC insulated copper wire complete in all respects	75Meter		

CONDITIONS OF QUOTATIONS

1. Rate shall be inclusive GST & other all taxes and free delivery of university campus.
2. Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
3. In case of delay of work penalty upto 10% quoted cost may be imposed.
4. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid this account.
5. Work to be done strictly as per drawings and specifications and direction of the university Engineer.
6. Departmental Notice Board.
7. Incharge, AKMU.
- 8.


(Naushad Khan)
Incharge