

# UNIVERSITY ENGINEERING DEPARTMENT

Chandra Shekhar Azad University of Agriculture & Technology, Kanpur-2

No.CSAE-1185/F.No.26/VC Camp/2020-21-22 प्रथम

Dated:March 14 ,2022

Sealed quotations are invited by Registered/Speed Post or by Courier for the following work by 21.03.2022 before 2:00 pm. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Incharge, University Engineering in this deptt. on any working day in office hours from 14.03.2022. Quotations will be opened on 21.03.2022 at 3:00 PM in presence of those quotationers who may like to be remain at that time.


University reserves the right to reject any or all the quotations without assigning any reason.

## Work : Miscellaneous Electric Works in V.C. Camp Office & Residence

Sl.No.	Description of Item	Qty.	Rate	Amount
1/131(C)	<b>Wiring Point</b> for light with 1.5Sqmm FRLSH PVC insulated multistrand single core copper conductor cable in heavy gauge PVC conduit with 1.5Sqmm PVC insulated copper wire as earthwire complete with Piano type switch ceiling rose batten Holder complete in all respects.	06nos.		
2/405	<b>S&amp;F</b> of batten/Angle Holder complete in all respects	06nos.		
3.	<b>Supply &amp; Wiring</b> of submain with 2no. 2.5Sqmm PVC insulated multistrand copper conductor wire in PVC conduit with one no 1.5Sqmm PVC insulated copper wire as earthwire drawn in conduit.	25Meter		
4.	<b>S&amp;F</b> of 23watt, 240volt LED bulb on existing lights and as required	25nos.		
5/1203(A)	<b>S&amp;F</b> of Electronic fan regulator 120-280V ISI marked on the existing switch board including making connections required material T&P etc.	02nos.		
6/1002	<b>S&amp;F</b> of 6 to 32 Amp SPMCB(10KA)	06nos.		
7/1005(B)	<b>S&amp;F</b> of 63Amp DP Isolator Cat A	02nos.		
8.	<b>Repairing &amp; Fixing</b> of fountain lights including proper erection & testing complete in all respects	03nos.		
9.	<b>S&amp;F</b> of 4Module GI concealed board and erection & testing of modular switch etc.	04nos.		

### CONDITIONS OF QUOTATIONS

1. Rate shall be inclusive GST & other all taxes and free delivery of university campus.
2. Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
3. In case of delay of work penalty upto 10% quoted cost may be imposed.
4. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid this account.
5. Work to be done strictly as per drawings and specifications and direction of the university Engineer.
6. Departmental Notice Board.
7. Incharge, AKMU.

  
(Naushad Khan)  
Incharge