

**University Engineering Department**  
**Chandra Shekhar Azad University of Agriculture & Technology Kanpur**

No. CSAE 44 / 21-22(R-1)

Dated- 19 April 2022

Sealed quotations are invited by registered/speed post or by Courier for the following work by 22.04.2022 before 2:00 PM. Quotation by ORDINARY POST or BY HAND will not be accepted. Blank quotation form can be taken from the In Charge (Works) in this deptt. on any working day in office hours from 19.04.2022 Quotations will be opened on 22.04.2022 at 3:00 PM in presence of those quotationers who may like to be remain at that time.

University reserve the right to reject any or all the quotations without assigning any reason.

**NAME OF WORK:-** Construction of Main hole/ cleaning of sewer line/ gully trap and cover of main hole at S N hostel of home science at CSAU Kanpur Campus

SNo	Description	Qty	Unit	Rate(Rs.)	Amount (Rs.)
1	Earth work in excavation in trenches for foundations pipes cable etc. in ordinary soil (loan clay or sand) including lift upto 1.5 m lead upto 50 m and dressing of sides and ramming of bottom and disposal of surplus excavated earth as directed by the engineer I/c within a lead of 50 m	8.50	Cubic Metre		
2	providing and laying in cement concrete 4:2:1 of not less than strength of M150 [stone ballast of 20 mm thick, nominal size stone grit instade of 4 cm, stone ballast ): 2 approved coarse sand : 1 cement] and curing complete, including cost of formwork in foundation and floors	1.70	Cu.M		
3	class 150 brick work in 1:4 cement and coarse sand in super structure above plinth level upto floor two level including necessary and moulding of brick work thickness of wall more than 12 cms including supply of all material labour and T&P etc required for proper completion of the work	1.50	Cu. M		
4	RCC work with cement approved portin at 2 cm gauge approved stone ballast in the proportion 1:2:4 (1 cement: 6 aggregate) in slabs excluding supply of reinforcement and its bending the same with 24 BWGGI, binding wire and necessary centering and shuttering etc and also including supply of all materials labour and T&P etc. required for proper completion of the work	0.40	Cu. M		
5	Suppny and fixing of 6 inch PVC pipe of supreme make i/c fixing and jointing the main hole complete work	20	metre		
6	Cleaning of Main hole i/c chock sewer line etc comple including malba/ kachra away from 60 mt form the site	11	No		
7	Mild steel or iron iin plain work such as reinforced concrete or reinforced brick work brought to required shape as necessary including bending for proper completion of the work and including supply of steel its wastage bend hooks and authorized overlapping shall be measured upto floor level	30.00	Kg		
8	Cleaning of Gully trap for bathroom i/c dismantling work etc including malba/ kachra away from 60 mt form the site	01	No		

**CONDITIONS OF QUATATIONS:**

1. Rate shall be inclusive of all taxes and free delivery of University Campus.
2. Work shall be resumed within 03 days of the place in order and entire work to be complete within month.
3. In case of delay of work penalty upto 10% quoted cost may be imposed.
4. Quantities are liable to vide variations on either side even items may be all together omitted be compensation will be paid this account.
5. Work to be done strictly as per drawing and specifications and direction of the officer In Charge.
6. Copy to Notice Board.
7. Incharge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur upload for Univ. website.

(Naushad Khan)  
Officer In Charge