

University Engineering Department
Chandra Shekhar Azad University of Agriculture & Technology Kanpur

No. CSAE 339 / 22-23(R-1)

Dated- 10 June 2022

QUOTATION NOTICE

Sealed quotations are invited by registered/speed post or by Courier for the following work by 16.06.2022 before 2:00 PM. Quotation by ORDINARY POST or BY HAND will not be accepted. Blank quotation form can be taken from the In Charge (Works) in this deptt. on any working day in office hours from 10.06.2022. Quotations will be opened on 16.06.2022 at 3:00 PM in presence of those quotationers who may like to be remain at that time.


University reserve the right to reject any or all the quotations without assigning any reason.

NAME OF WORK:- Construction of Boundary wall behind the Forestry Department at CSAU campus Kanpur

SNo	Description	Qty	Unit	Rate(Rs.)	Amount (Rs.)
1	Earth work in excavation in trenches for foundations pipes cable etc. in ordinary soil (loan clay or sand) including lift upto 1.5 m lead upto 50 m and dressing of sides and ramming of bottom and disposal of surplus excavated earth as directed by the engineer I/c within a lead of 50 m	23.00	Cubic Metre		
2	Class-150 brick work in 1:4 cement and Coarse sand of 1.25 fineness modulus mortar in foundation and plinth including supply of all materials, labour and tools and plants etc. required for proper completion of the work	7.50	Cubic Metre		
3	2.5 cm thick damp proof course with cement and approved coarse sand 1:2 and including water proofing materials as ordered by the Engineer-in-Charge in the proportion as specified by the manufacturer including supply of all material, labour and tools and plants etc. required for proper completion of the work including proper curing and shuttering as necessary	5.00	Square Metre		
4	Class 150 brick work in 1:4 cement and coarse sand in super structure above plinth level upto floor two level including necessary and moulding of brick work thickness of wall 12 cm and below including supply of all material labour and T&P etc required for proper completion of the work	4.50	Cubic Metre		
5	12 mm cement plaster in 1 cement:3 coarse sand plaster upto floor two level including internal rounded angles chamfers and rounded angles not exceeding 80 mm in girth and finished even and smooth	95.00	Square Metre		

CONDITIONS OF QUATATIONS:

1. Rate shall be inclusive of all taxes and free delivery of University Campus.
2. Work shall be resumed within 03 days of the place in order and entire work to be complete within month.
3. In case of delay of work penalty upto 10% quoted cost may be imposed.
4. Quantities are liable to vide variations on either side even items may be all together omitted be compensation will be paid this account.
5. Work to be done strictly as per drawing and specifications and direction of the officer In Charge.
6. Copy to Notice Board.
7. Incharge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.


(Naushad Khan)
Officer In Charge