

**University Engineering Department**  
**Chandra Shekhar Azad University of Agriculture & Technology Kanpur**

No. CSAE 918 /F.No.35/कैलाश भवन / 2021-22

Dated: 30-12-2022

**QUOTATION NOTICE**

Sealed quotations are invited by registered/speed post or by Courier for the following work by 03.01.2022 before 2:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer Incharge, University Engineering deptt. on any working day in office hours from 30.12.2022. Quotations will be opened on 03.01.2023 at 3:00 PM in presence of those quotationers who may like to be remain at that time.


University reserve the right to reject any or all the quotations without assigning any reason.

**Name of work:- Estimate For lighting Arrangement of Kailash Bhawan & administrative building varahdah's.**

SNo.	Description	Qty	Rate(Rs.)	Amount (Rs.)
1.	S&F 36 watt fluorescent tube light Philips make ISI.	20 Nos		
2.	S&F of 36 watt Electronic choke Philips/Havells.	15 NOS		
3.	S&F of 9 watt LED bulb Philips/Havells.	25 Nos		
4./405	S&F of batten/Angle Holder complete in all respects	15 Nos		
5./141 3	S&F of LED Tube Light with metal body heavy duty box type batten light fitting 1x22 watt LED Polycarbonate tube light complete including tube suitable for both surface & suspended complete in all respects. Cat AAA Philips Make.	10 Nos		
6.	S&F of 23 watt LED bulb Philips Make.	15 Nos		
7.	S&F of 6Amp Modular switch on existing switch board crab tree Athena.	12 Nos		
8/218 (c)	Supply & wiring of submain with 2 no.10sq.mm FRLSH Pvc insulated single core copper conductor cable in 25 mm dia Pvc conduit with one no.6 sq-mm. Pvc insulated copper wire complete in all respects.	30.00 meter		
9/1405	S&F of Pendent/suspended mounting 24 watt to 32 watt LED hanging light having Powder coated die cast aluminium housing with heat sink di ffuser/ reflector and driver set, suitable for 24 hours continuous operation complete in all respects CAT AAA Philips/Crompton.	10Nos		
	Total			
	AddGST 18%			
	Add labour Cess@1%			
	<b>Grand Total</b>			

**CONDITIONS OF QUATATIONS:**

1. Rate shall be inclusive GST & other all taxes and free delivery of University Campus.
2. Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
3. In case of delay of work penalty upto 10% quoted cost may be imposed.
4. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid this account.
5. Work to be done strictly as per drawing and specifications and direction of the University Engineer. .
6. Copy to Notice Board.
7. Incharge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.

  
**(Naushad Khan)**  
**Officer In Charge**