

University Engineering Department

Chandra Shekhar Azad University of Agriculture & Technology Kanpur

No. CSAE- 814 /2024-25

Dated: 22-01-2025

QUOTATION NOTICE

Sealed quotations are invited by registered/speed post or by Courier for the following work by 27.01.2025 before 2:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer In-charge, University Engineering department on any working day in office hours from 22.01.2025. Quotations will be opened on 27.01.2025 at 3:00 PM in presence of those quotationers who may like to be remain at that time.

University reserves the right to reject any or all the quotations without assigning any reason.


Name of work: Construction of Soak pit & water supply system in Bathroom of Agriculture extension & Economics department at CSA University Campus Kanpur

S.L. No	Description of Item	QTY	UNIT	Rate as	Amount
1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level 1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded stone aggregate 20 mm nominal size derived from natural sources)	1.00	cu.m		
2	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-incharge. All kinds of soil	30.00	Cu.m		
3	Brick work with non modular fly ash bricks conforming to IS:12894, class designation 10 average compressive strength in super structure above plinth level up to floor V level in Cement mortar 1:6 (1 cement : 6 Coarse sand) including supply of all material labour and T&P etc required for proper completion of the work.	4.50	Cu. M		
4	S/F of PVC pipe 4"	10.00	Mtr		
5	S/F of PVC cover cap	01	No		
6	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	1.00	Cu. M		
7	Fixing of rain water pipes complete in all respect as per direction of EIC	1	Job		
8	Steel reinforcement of RCC work i/c straightening, cutting, bending, placing, in position and binding all complete upto plinth level.	75.00	kg		
9	S/F of ½ inch valve cock PVC	01	No		
10	S/F of ½ inch low down washer PVC	01	NO		
11	S/F of Tap	05	NOs		
12	S/F of 2 inch pipe PVC	06	Ft		
13	S/F of 2 inch elbow PVC	04	No		
14	S/F of 1 inch low down washer	02	No		
15	S/F of PVC ballcock	01	No		
16	S/F of Water tank 500 litre cover supreme grade	01	No		
17	S/F of Cleaning of Chamber	1	Job		
18	S/F of Teflon tape	20	No		
19	S/F of solution	250	gram		
20	S/F of Toti	03	No		
21	S/F of waste pipe ¼ inch	13.00	Ft		
22	S/F of PVC connection 18 inch	03	No		
23	S/F of PVC low down ball cock	01	No		
24	S/F of 2 inch pipe urinal	06	ft		
25	S/F of pillar cock	01	no		
26	S/F of ½ inch GI socket	01	No		
27	S/F of ¼ inch CP waste jaali	01	No		

28	S/F of 3 inch GI nipple	01	No	
				Total
				Add GST 18%
				Add 1 % Labour Cess
				Grand Total
				Say

CONDITIONS OF QUATATIONS:

1. The firms are requested to mention their GST number on their Pads it is compulsory to write the GST number on the Quotation.
2. Rate shall be inclusive GST & other all taxes and free delivery of University Campus.
3. Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
4. In case of delay of work penalty up to 10% quoted cost may be imposed.
5. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid this account.
6. Work to be done strictly as per drawing and specifications and direction of the University Engineer. .
7. Copy to Notice Board.
8. Incharge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.


(Naushad Khan)
Officer In Charge