

**University Engineering Department**  
**Chandra Shekhar Azad University of Agriculture & Technology Kanpur**

No. CSAE **707** /F.No.26 VC Camp/2020-21-22-25

Dated: **16/01**, 2025

**QUOTATION NOTICE**

Sealed quotations are invited by registered/speed post or by Courier for the following work by 20.01.2025 before 2:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer in Charge, University Engineering deptt. on any working day in office hours from 10.00 AM to 4.00 PM. Quotations will be opened on 20.01.2025 at 3:00 PM in presence of those quotationers who may like to be remain at that time.


University reserve the right to reject any or all the quotations without assigning any reason.

**Name of work:- Revised Estimate UG Computer Lab at CSAU Campus Kanpur.**

S.No	Description	Qty	Rate(Rs.)	Amount (Rs.)
1	S&F of 23 Watt red bulb PHILIPS make	05 Nos		
2	S&F 48 Ceiling Fan orient make double ball bearing ISI	05 Nos		
3	S&F of 100 Amp TPN 4 pole isolater legrand Havells ISI CAT A	02 Nos.		
4	S&F of LED tube Lite with metal body heavy duty box type buttan light fitting 1x25 watt LED Polycarbonate tube light complete including tube. Etc on surface complete in all respects Philips make.	04 Nos		
5	S&F of 100 Amp 4 pole change over switch on 50mmx50mmx6mm angle iron for the cost of labour T&P painting and other material required for proper completion of work as per direction of etc havells make.	01 Nos		
6	S&F of 6Amp to 32 amp SP MCB 10kva curve 1 earned Havells CAT A	05 Nos		
7	S&F of electronic fan dimmer Modular 300/400 watt isi marked on the existing switch board including making connections required material labour T&P etc. for proper complication of work to the satisfaction of engineer in charge of work.	05 Nos		
8	S&F of power plug with 20amp /250 volt flush type modular switch and 5 pin 20 A/250 volt flush type universal modular socket switch on concealed M.S. box including supply of all material labour T&P etc. required for proper complication of work	05 Nos.		
9	Shifting of 5KVA UPS exiting place wiring and connection proper complete in all respects	01 Job		
10	S&W of submain with 2 nos 10 sqmm FRESH pvc insulated 1100 volt grade multistand copper conductor cable in heavy gauge pvc conduct concealed with one no.6 sqmm FRESH pvc insulated multistand copper conductor cable as earth wire drawn in conduit.	10 Mtr.		
<b>Total</b>				
GS1518%				
Addl. labour cess @ 1%				
<b>Total Amount Rs.</b>				

**CONDITIONS OF QUATATIONS:**

- Rate shall be inclusive GST & other all taxes and free delivery of University Campus.
- Work shall be resumed within 05 days of the plage in order and entire work to be complete within month.
- In case of delay of work penalty upto 10% quoted cost may be imposed.
- Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid this account.
- Work to be done strictly as per drawing and specifications and direction of the University Engineer.
- Copy to Notice Board.
- Incharge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.

  
**(Naushad Khan)**  
**Officer In Charge**