

**University Engineering Department**  
**Chandra Shekhar Azad University of Agriculture & Technology Kanpur**

No. CSAE- 89 /2024-25

Dated: 18/02,2025

**QUOTATION NOTICE**

Sealed quotations are invited by registered/speed post or by Courier for the following work by 20.02.2025 before 2:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer In-charge, University Engineering department on any working day in office hours from 17.02.2025. Quotations will be opened on 20.02.2025 at 3:00 PM in presence of those quotationers who may like to be remain at that time.


University reserves the right to reject any or all the quotations without assigning any reason.

**Name of work:** Fencing work and Iron gate etc Near Soil Conservation & Water Management Department at CSA University Campus Kanpur

S.L. No	Description of Item	QTY	UNIT	Rate as	Amount
1	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in-charge Made of G.I. wire of dia 4 mm	15.00	sqm		
2	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge: All kinds of soil	2.20	Cu.m		
3	S/F of Iron gate (Iron pipe Door/Grill (2"X2" pipe frame and 2"X1" size square pipe on Door/Grill ie Painting etc) complete in all respect as per instruction of EIC	220.00	Kg		
4	S/F of heavy Bush for gate	06.00	no		
5	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size de rived from natural sources)	1.00	Cu. M		
6	12 mm cement plaster of mix 1:6 (1 cement: 6 fine sand)	5.00	Sq. M		
7	Finishing walls with Premium Acrylic Smooth exterior paint with Silicone additives of required shade: New work (Two or more coats applied @ 1.43 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	10.00	Sq.M		
8	Steel reinforcement of RCC work i/c straightening, cutting, bending, placing, in position and binding all complete upto plinth level.	110.00	kg		
Total Rs ( after deduction of Item No 3&4)					
GST Factor calculation(total Rs X 112 X 0.735/107)					
Index Number Calculation+ Item No 3&4					
Total					
Add GST 18%					
Add 1 % Labour Cess					
Grand Total					
Say					

**CONDITIONS OF QUATATIONS:**

1. The firms are requested to mention their GST number on their Pads it is compulsory to write the GST number on the Quotation.
2. Rate shall be inclusive GST & other all taxes and free delivery of University Campus.
3. Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
4. In case of delay of work penalty up to 10% quoted cost may be imposed.
5. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid this account.
6. Work to be done strictly as per drawing and specifications and direction of the University Engineer.
7. Copy to Notice Board.
8. In charge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.

  
**(Naushad Khan)**  
**Officer In Charge**