

**University Engineering Department**  
**Chandra Shekhar Azad University of Agriculture & Technology Kanpur**

No. CSAE- 124 /2025-26

Dated: 14/05,2025

**QUOTATION NOTICE**

Sealed quotations are invited by registered/speed post or by Courier for the following work by 21.05.2025 before 2:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer In-charge, University Engineering department on any working day in office hours from 14.05.2025 Quotations will be opened on 21.05.2025 at 3:00 PM in presence of those quotationers who may like to be remain at that time.


University reserves the right to reject any or all the quotations without assigning any reason.

**Name of work:** Painting and other repairing works in Residence C-40 at CSA University Campus Kanpur.

Sl. No	Description of Item	QTY	UNIT	Rate	Amount
1	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	96.29	Sq. M		
2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:3 (1 cement :3 coarse sand)	6.88	SqM		
3	12 mm cement plaster of mix 1:6 (1 cement:6 fine sand)	50.13	Sq.M		
4	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 liters/10 sqm complete including cost of Priming coat.	96.29	Sq M		
5	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture	5.38	Sq.m		
6	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15 mm C.P. brass pillar taps	01	No.		
7	S/F of PVC Water Storage tank 500 ltr 3 Layer Heavy Duty of Sintex Make for proper completion of work in all respect as per direction of EIC	01	Nos.		
8	S/F of Mosquito net in window for proper completion of work in all respect as per direction of EIC	1.91	Sq.m		
9	S/F of MS grill with all material, labour, T&P etc for proper completion of work in all respect as per direction of EIC	10	Kg.		
10	S/F of PVC door shutter with chaukhat of approved make with all fitting complete in all respect as per direction of EIC	2.70	Sq.m		
11	Renewing glass panes, with putty and nails wherever necessary including racking out the old putty: Float glass panes of nominal thickness 4 mm (weight not less than 10kg/sqm)	0.56	Sq.m		
12	Providing and fixing ISI marked flush door shutters conforming to IS : 2202 (Part I) non-decorative type, core of block board construction with frame of 1st class hard wood and well matched commercial 3 ply veneering with vertical grains or cross bands and face veneers on both faces of shutters: 30 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.	1.62	Sq.m		
	Total Rs				
	Add GST 18%				
	Add 1 % Labour Cess				
	Grand Total				

**CONDITIONS OF QUATATIONS:**

- The firms are requested to mention their GST number on their Pads it is compulsory to write the GST number on the Quotation.
- Rate shall be inclusive GST & other all taxes and free delivery of University Campus.
- Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
- In case of delay of work penalty up to 10% quoted cost may be imposed.
- Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be pai this account.
- Work to be done strictly as per drawing and specifications and direction of the University Engineer.
- Copy to Notice Board.
- In charge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.

  
 प्रभारी अधिकारी  
 विश्वविद्यालय अभियंत्रण विभाग  
 च०श०आ० कृषि एवं प्रौ०वि०वि०  
 कानपुर-2