

University Engineering Department
Chandra Shekhar Azad University of Agriculture & Technology Kanpur

No. CSAE- 110 /2025-26

Dated: 09/05,2025

QUOTATION NOTICE

Sealed quotations are invited by registered/speed post or by Courier for the following work by 14.05.2025 before 2:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer In-charge, University Engineering department on any working day in office hours from 09.05.2025. Quotations will be opened on 14.05.2025 at 3:00 PM in presence of those quotationers who may like to be remain at that time.


University reserves the right to reject any or all the quotations without assigning any reason.

Name of work: Painting and other repairing works in Dr. Ekta Sharma office chamber and PVC flooring work in other office room of Home science Textile department at CSA University Campus Kanpur

S.L. No	Description of Item	QTY	UNIT	Rate	Amount
1	12 mm cement plaster of mix 1:6 (1 cement:6 fine sand)	1.00	Sq. M		
2	Removing white or colour wash by scrapping and sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete	74.90	SqM		
3	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications : Two or more coats applied on walls @ 1.25 ltr/10 sqm over and including one coat of Special primer applied @ 0.75 ltr /10 sqm	149.79	Sq.M		
4	Finishing with Deluxe Multi surface paint system for interiors and exteriors using Primer as per manufacturers specifications Painting wood work with Deluxe Multi Surface Paint of required shade. Two or more coat applied @ 0.90 ltr/10 sqm over an under coat of primer applied @0.75 ltr/10 sqm of approved brand and manufacture	16.20	Sq M		
5	Painting Steel work with Deluxe Multi Surface Paint to give an even shade. Two or more coat applied @ 0.90 ltr/ 10 sqm over an under coat of primer applied @ 0.80 ltr/ 10 sqm of approved brand and manufacture	18.45	Sq.m		
6	S/F of 2 mm thick PVC Matt of Approved quality & design/Shape/color as Direction of EIC	53.13	Sq m		
				Total Rs	
				Add GST 18%	
				Add 1 % Labour Cess	
				Grand Total	

CONDITIONS OF QUATATIONS:

1. The firms are requested to mention their GST number on their Pads it is compulsory to write the GST number on the Quotation.
 2. Rate shall be inclusive GST & other all taxes and free delivery of University Campus.
 3. Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
 4. In case of delay of work penalty up to 10% quoted cost may be imposed.
 5. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be pai this account.
 6. Work to be done strictly as per drawing and specifications and direction of the University Engineer.
 7. Copy to Notice Board.
8. In charge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.


(Naushad Khan)
Officer In Charge