

University Engineering Department
Chandra Shekhar Azad University of Agriculture & Technology Kanpur

No. CSAE 119 /F.No.26 II- VC Camp -25-26

Dated: 14/05, 2025

QUOTATION NOTICE

Sealed quotations are invited by registered/speed post or by Courier for the following work by 19.05.2025 before 2:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Office of Incharge, University Engineering deptt. on any working day in office hours from 14.05.2025. Quotations will be opened on 19.05.2025 at 3:00 PM in presence of those quotationers who may like to be remain at that time.


University reserve the right to reject any or all the quotations without assigning any reason.

Name of work:-Estimate For Electric Repairing Office of Dr. Ekta Sharma & Textile Lab, Home Science deptt.

S.No.	Description	Qty	Rate (Rs.)	Amount (Rs.)
1/405	S&F of batten/angle holder complete in all respects.	08 Nos		
2.	S&F of 6Amp F/T switch Anchor Make.	25 Nos		
3.	S&F of 6Amp F/T socket Anchor Make.	08 Nos		
4.	S&F 2.5 Mfd condenser complete Havells Make.	09 Nos		
5.	Replacement of Heavy duty G I Switch board concealed in wall complete in all respects.			
	(i) 33x17 cm	03 Nos		
	(ii) 8"x10"	06 Nos		
6.	S&F of 15 watt LED bulb Philips Make.	12Nos		
7.	S&F of AC power plug with 25Amp MCB & 25Amp ACB and plug complete crab tree make.	01 Nos		
8/1139(A)	S&F of power plug with 20Amp/250Volt Flush type modular switch and 5 pin 20A/ 250Volt Flush type modular socket with complete modular box including supply of all material Labour T&P etc.required proper completion of work.	08 Nos		
9/1006(c)	S&F of 63Amp TP isolator Havells/Legrand	03 Nos		
10/1002	S&F of 6 to 32 Amp SP MCB 10KAC curve Legrand	10 Nos		
11/1413	S&F of LED tube light with metal body heavy box type batten light fitting 1x25 watt LED Poly carbonate tube light complete including tube suitable for both surface/suspended catAAA Philips Make.	11 Nos		
12.	Rewinding of ceiling fan existing complete in all respects.	04 Nos		
13.	Supply & Wiring of submain with 2Nos. 6 Sq.mm.copper conductor FRLSH multistrand wire with one no. 4sqmm copper in conductor complete in all respects	40 mtr.		
14/1203(c)	S&F of Electronic Fan regulator (Modular) dimmer 120-280Volt ISI marked on the existing Switch board including making connections required material Labour T&P etc.For completion of work.	09 Nos		
	Total Rs.			
	AddGST.@18%			
	Labour cess1%			
	Total Rs.			

CONDITIONS OF QUATATIONS:

- Rate shall be inclusive GST & other all taxes and free delivery of University Campus.
- Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
- In case of delay of work penalty upto 10% quoted cost may be imposed.
- Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid this account.
- Work to be done strictly as per drawing and specifications and direction of the University Engineer. .
- Copy to Notice Board.
- Incharge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. websi


(Naushad Khan)
Officer In Charge