

**University Engineering Department**  
**Chandra Shekhar Azad University of Agriculture & Technology Kanpur**

No. CSAE- 197 /2025-26

Dated: 05/06,2025

**QUOTATION NOTICE**

Sealed quotations are invited by registered/speed post or by Courier for the following work by 11.06.2025 before 2:00 PM. Quotation by **ORDINARY POST** or **BY HAND** will not be accepted. Blank quotation form can be taken from the Officer In-charge, University Engineering department on any working day in office hours from 04.06.2025. Quotations will be opened on 11.06.2025 at 3:00 PM in presence of those quotationers who may like to be remain at that time.

University reserves the right to reject any or all the quotations without assigning any reason.


Name of work: Construction of Retting Tank (5ftX5ftX4ft) in Basic Science College at  
 CSA University Campus Kanpur

Sl. No	Description of Item	QTY	UNIT	Rate	Amount
1	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and lift upto 1.5 m, as directed by Engineer-in-charge. All kinds of soil	9.44	Cu.m		
2	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources)	0.56	Cum		
3	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	2.94	Cum		
4	12 mm cement plaster of mix 1:6 (1 cement:6 fine sand)	9.48	Sq. M		
5	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement, including cement slurry, but excluding the cost of nosing of steps etc. complete. 11.3.1 40 mm thick with 20 mm nominal size stone aggregate	2.25	Sqm		
				Total Rs	
				Add GST 18%	
				Add 1 % Labour Cess	
				Grand Total	

**CONDITIONS OF QUATATIONS:**

1. The firms are requested to mention their GST number on their Pads it is compulsory to write the GST number on the Quotation.
2. Rate shall be inclusive GST & other all taxes and free delivery of University Campus.
3. Work shall be resumed within 05 days of the place in order and entire work to be complete within month.
4. In case of delay of work penalty up to 10% quoted cost may be imposed.
5. Quantities are liable to wide variations on either side even items may be all together omitted be compensation will be paid this account.
6. Work to be done strictly as per drawing and specifications and direction of the University Engineer.
7. Copy to Notice Board.
8. In charge A.K.M.U., C.S.A.U. of Ag & Tech Kanpur uploads for Univ. website.



  
 (Naushad Khan)  
 Officer In Charge